

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 13 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Zeigler Well No. # 4

Location C NW SE Sec. 28 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4898'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 6:00 AM Day 11th Month Sept, Year 1965

The Above well was plugged as follows:

546' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was at 160'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 300', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

**INVOICED**

DATE 9/13/65

INV. NO. 1990-W