

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Comp. 1-19-35
API NUMBER 15-095-97916

LEASE NAME Miles "B"

WELL NUMBER 6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Lin

440 Ft. from E Section Lin

SEC. 19 TWP. 27 RGE. 10 COR(W

COUNTY Kingman

Date Well Completed 1-19-35

Plugging Commenced 10-14-88

Plugging Completed 10-22-88

LEASE OPERATOR TEXACO INC. FOR
TEXACO PRODUCING INC.

ADDRESS P.O. BOX 2420, TULSA, OK 74102

PHONE#(918) 560-6000 OPERATORS LICENSE NO. 4742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Shari Feist Albrecht (KCC District Agent's Name).

Is AGO-1 filed? YES If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top 3465 Bottom 3519 T.D. 3519'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing-KC		3465'	317'	7"	---	None
		317'	9'	12-1/2"	---	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each, so from 3500' to 3415' filled with sand; 3415' to 3362' with 10 sx common cement; 3362' to 2512' gel; from 2512' to 2454' 10 sx sur-fil cement; from 2454' to 2007' with gel; 2007' to 9' with 20 sxs common cement with 400# hulls, 70 sx sur-fil cement, 995 sx of 60/40 POZ with 1200# hulls casing cut off at 9' below ground level, welded on steel flange. Filled w/native dirt, cleaned. (If additional description is necessary, use BACK of this form.) leveled location.

Name of Plugging Contractor TEXACO INC. FOR
TEXACO PRODUCING INC. License No. 4742

Address P.O. BOX 2420, TULSA, OK 74102

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

JOHN K. HAMBY

(Employee of Operator) or (Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) John K. Hamby
(Address) John K. Hamby
P.O. BOX 2420, TULSA, OK 74102

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 89

RECEIVED
STATE OF KANSAS

Elizabeth R. Legg
Notary Public

Commission Expires: July 21, 1991

CONSERVATION DIVISION
Wichita, Kansas

ELIZABETH R. LEGG
By Commission Expires
July 21, 1991