


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 6 Twp. 27 Rge. 12 (E) (W)
Location as "NE/CNW&SW&" or footage from lines NE NE SW
Lease Owner Raymond Oil Co., Inc.
Lease Name Beck A#3 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10/4/73 _____ 19____
Plugging completed 10/15/73 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4249 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				85/8	396	none
				5"	4238	3099'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 4200' and dumped 5 sacks cement. Shot pipe at 3253', 3160', pulled 97 joints of 5 1/2" casing. Halliburton pumped 3 sacks hulls, 10 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 73

My commission expires _____

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

Beck #3A

Owner: Cooperative Refinery Association
Contractor: Earl F. Wakefield
Comm: 8-8-51 Comp: 8-31-51

NE NE SW 6-27-12
Pratt County, Kansas
Casing:
396' of 8 5/8"
4238 1/2' of 5 1/2"

Elevation 1874 D.F.

Sand & Red Bed	325
Red Rock and Shells	396
Red Bed, Sand & Shale	676
Red Bed, Shale & Sand	950
Shale & Shells	1225
Shale, Salt & Shells	1710
Shale & Shells	1800
Lime	1860
Lime & Shale	1970
Shale	2090
Lime	2125
Shale	2135
Sand & Sandy Lime	2190
Shale & Lime	2230
Lime & Shale	2295
Lime	2355
Lime & Shale	2490
Lime & Sandy Shale	2640
Lime & Shale	2825
Lime	2990
Lime & Shale	3105
Lime	3230
Lime & Shale	3335
Shale	3340
Lime & Shale	3429
Sandy Shale	3485
Shale	3515
Lime & Shale	3610
Shale	3670
Lime	3986
Lime & Shale	4056
Lime	4140
Lime & Chert	4187
Shale	4194
Shale & Chert	4203
Sand	4249
Total Depth	4249

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1973
CONSERVATION DIVISION
Wichita, Kansas

4249
1874
11/27

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Beck #3A well located NE NE SW 6-27-12, Pratt County, Kansas.

F. L. Barker

Subscribed and sworn to before me this 6th day of September, 1951.

E. Jeanie Jeffrey

My Commission Expires: 12-23-54