

STATE OF KANSAS
STATE CORPORATION COMMISSION
300 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-155-21,129-00-02

LEASE NAME HA Krehbiel

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 26 RGE. 6W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 11-9-01

Plugging Completed 11-12-01

LEASE OPERATOR W.R. ALLAM 11-29-2001

ADDRESS P.O. Box 2325 Hutchinson, Kansas 67504

PHONE#(620) 663-2337 OPERATORS LICENSE NO. 5808

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on _____ (date)

Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4040'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	231'	None
				5-1/2"	4038'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3200' and 5 sacks cement. Shot pipe @2500', pulled up to 900'; pumped 35 sacks cement and 10 sacks gel, pulled up to 400', pumped 35 sacks cement, pulled up to 280' and circulated cement to the surface. 60/40 pos. 4% gel Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: W.R. Allam

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of November, 2001

Irene Herzberg
Notary Public

My Commission Expires:

