

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-155-01958-0000

RECEIVED  
STATE CORPORATION COMMISSION  
7-20-1957  
JUL 20 1957  
CONSERVATION DIVISION

NORTH

		X	

Locate well correctly on above  
Section Plat

Reno County. Sec. 14 Twp. 26 S. Rge. 8 W (E)  
Location as "NE/CNW/SW" or footage from lines C SW/4 SE/4  
Lease Owner J. Goldstein  
Lease Name Graber Well No. 1  
Office Address 1165 Grant St., Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-16-57 19  
Application for plugging filed 7-16-57 19  
Application for plugging approved 7-16-57 19  
Plugging commenced 7-16-57 19  
Plugging completed 7-16-57 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3675 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned pits. Circulated 1 hour to bring heavy mud around. Layed down drill pipe. Solid rock and hull bridge built 250', with 15 sacks cement run through drill pipe top plug. Hull in sack wired to rotary table with 6 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mr. Ruel Durkee  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
J. Goldstein (Employer or Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Goldstein  
1165 Grant St. Denver Colo  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 57

My commission expires October 21, 1960  
Maxine Condon Notary Public.

PLUGGING  
FILE SEC 14 T 26 R 6W  
BOOK PAGE 30 LINE 8

CHERRY DRILLING CO., INC.  
102 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 20 1957  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-155-01958-0000

ROTARY DRILLING LOG

Lease: Graber

Contractor: Cherry Drilling Co., Inc.  
102 Insurance Bldg.  
Wichita, Kansas

Well: #1

Location: C SW/4 SE/4  
Sec. 14 T 26 S R 6 W  
Reno County, Kansas

Surface Pipe: 9 Joints Used Surface Pipe  
8 5/8" - 269' overall less  
threads, cemented with 200 sacks  
regular cement, 2% c.c.  
Circ. Plug down.

Elevation:

Well Commenced: July 6, 1957  
Completed: July 16, 1957

Casing: D & A  
Gunned pits. Circ. 1 hr. to bring  
heavy mud around. Lay down d. p.  
Built solid rock & hull bridge  
250 feet. 15 Sks cement run through  
drill pipe top plug. Hull in  
sack wired to rotary table 6 sks  
cement.

Company: J. Goldstein  
1165 Grant Street  
Denver, Colorado

\* \* \* \* \*

0-265		2980-3035	lime
265-665	shale	3035-3335	lime
665-1045	shale, shells, lime	3335-3415	lime, sand
1045-1095	lime, shale	3415-3555	lime
1095-1390	lime	3555-3610	lime, shale
1390-2490	shale, lime	3610-3660	lime
2490-2855	lime	3660-3665	
2855-2980	lime, sand	3665-3675	chert & chat

T. D. 3675

\* \* \* \* \*

GEOLOGIST'S TOPS

MISSISSIPPI 3658' ROTARY TOTAL DEPTH 3675'

\* \* \* \* \*

The above is a true and correct log to the best of my knowledge.

Subscribed and sworn to before me on this 17th day of July, 1957.

My commission expires October 24, 1960.

*Maxine Condon*  
Maxine Condon Notary Public

PLUGGING  
FILE SEC 14 T 26 R 6W  
BOOK PAGE 30 LINE 8