

15-155-02128-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 14 Twp. 26 Rge. 6 W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C W2 NW NE

Lease Owner V. E. Wiggins

Lease Name J. Graber Well No. I

Office Address P.O. Box 191 Mc Pherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-8 1962

Application for plugging filed 8-7 1964

Application for plugging approved 8- 1964


Plugging commenced 9-21 1964

Plugging completed 9-28 1964

Reason for abandonment of well or producing formation went dry.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4000' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3998-	2,720'
				8 5/8"	256'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3632' to 3600'. Dumped 5 sx of cement. Mudded hole to 240'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION
Wichita, Kansas

9-30-1964

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 Kind St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 th day of September, 1964

My commission expires January 5, 1966

Notary Public.

413 LL-23616

WELL LOG

15-155-02128-0000

Operator: V. E. Wiggins

Contractor: Bea Drlg. Co.

Lease: J. Graber

Spud date: 2- 22- 62

Well No: 1 - 1530 KB , Elev.

Comp. w/ Rotary: 3-8-62

Location: C W2 NW NE 14- 26-6W

Casing Record:

County : Reno

8 5/8" @ 256' com. w/ 175 sk.
5 1/2" @ 3998' " 200 sk.

Figures Indicate Bottom of Formation

Surface " sand	40
Shale & lime stringers	460
Lime & shale	540
Lime & sd.	1025
Lime & shale	1120
Lime & "	1250
Lime & shale	2180
Lime	2250
Shale	2310
Lime	2600
Lime & Shale	2736
Sand & shale	2930
Lime & Shale	3625
Chert & Lime	3820
Shale	3974
Shale & Sand	3997
Dolomite	3998
Lime	4000
T.D.	4000

Note: Well tested in the Viola , making 2 B.O.P.H. with 40 B.W.P.H.

Plugged back to 3632 1/2'
Perforated from 3627' to 3630'

Recovered light show oil & gas with water.

Geological Tops:

Heebner sh.	2661
Douglas sd	2737
Lansing	2936
Mississippi	3626
Kinderhook	3822
Misner	3974
Viola lime	3998

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964

9-30-1964
CONSERVATION DIVISION
Wichita, Kansas.

corr 9-27-

corr 9-28-

Filed for application

~~8/7/64~~ 8/7/64