


15-155-20926-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County, Sec. 14 Twp. 26S Rge. 6 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE/4 NE/4 SW/4
Lease Owner Keener Oil Company
Lease Name Stucky Well No. 1
Office Address 320 South Boston, Suite 406, Tulsa, OK
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry hole
Date Well completed 3/20 1983
Application for plugging filed 3/20 1983
Application for plugging approved 3/20 1983
Plugging commenced 3/20 1983
Plugging completed 3/20 1983
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Lesli
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total Depth was 4030 feet. Set first plug at 720 feet with 40 sacks of common cement, 3% Calcium Chloride and 2% Gel; set second plug at 250 feet with 35 sacks; 10 sacks and a bridge set at 40 feet and 10 sacks in the rathole. Cement by Halliburton. Job completed at 11:15 p.m. on March 20, 1983.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor
K. S. Martin, President of Kaw Drilling Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. S. Martin
K. S. Martin, President 1010 Union Center
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1983.

Mary Susan Whaley
Mary Susan Whaley Notary Public.

My commission expires December 10, 1983

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1983

CONSERVATION DIVISION
Wichita, Kansas



OPERATOR: Keener Oil Company
 CONTRACTOR: Kaw Drilling Co., Inc.
 WELL NAME: #1 Stucky
 LOCATION: SE/4 NE/4 SW/4 Sec. 14-26S-6W
 Reno County, Kansas
 SPUD DATE: March 10, 1983
 COMPLETION DATE: March 30, 1983

15-155-20926-0000


960	1271	Shale and Shell
1710	1757	Shale and Shell
1930	2150	Shale and Lime
2467	2668	Shale and Lime
3040	3162	Shale and Lime
3342	3416	Shale and Lime
3570	3645	Shale and Lime
3752	3787	Shale and Lime
	4030	R.T.D.

Spud hole at 10:30 a.m. on March 10, 1983. Drilled 226 feet of 12 1/4 inch hole. Ran 5 joints of 8 5/8 inch casing (tallied at 211 feet). Set at 223 feet with 200 sacks of common cement, 3% Calcium Chloride and 2% Gel. Plug down at 5:15 p.m. on March 10, 1983.

Total Depth was 4030 feet. Set first plug at 720 feet with 40 sacks of common cement, 3% Calcium Chloride and 2% Gel; set second plug at 250 feet with 35 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Cement by Halliburton. Job completed at 11:15 p.m. on March 20, 1983.


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I, K. S. Martin, President of Kaw Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.




 K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 22nd day of March, 1983.



 Mary Susan Whaley, Notary Public

My Commission Expires:
 December 10, 1983



RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1983
 CONSERVATION DIVISION
 Wichita, Kansas