

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Reno County. Sec. 3 Twp. 26 Rge. 4 (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner Saturn Drilling, Inc.

Lease Name Nicklaus Well No. 2

Office Address 503 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 24 19 55

Application for plugging filed December 24 19 55

Application for plugging approved December 24 19 55

Plugging commenced December 24 19 55

Plugging completed December 24 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durakes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3315 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Lime Shell</u>	<u>Surface Pipe</u>	<u>0</u>	<u>199'</u>	<u>8 5/8"</u>	<u>12-14-55</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned Pits - circulated heavy mud around - layed down drill pipe - set bridge with hulls at 199' from top mixed 15X sacks cement through 6 joints drill pipe on top of bridge - fill hole with mud to 15' from bottom of cellar - made bridge with hulls and filled to bottom of cellar with 5 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
JAN - 1956  
CONSERVATION DIVISION  
Wichita, Kansas  
1-5-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Don Gardner (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

503 Union National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of January, 19 56

[Signature]  
Notary Public.

My commission expires November 21, 1956

PLUGGING  
FILE SEC 3 T26 R1W  
BOOK PAGE 26 LINE 40

1123456789  
FISH MARKET

D R I L L E R ' S   L O G  
 McKnab Drilling, Inc.  
 Nicklaus #2  
 SW SE NW Sec. 3-26S-4W  
 Reno County, Kansas

15-155-01951-0000

<u>FROM</u>	<u>TO</u>	
0	130	Shale & Shells
130	199	Shale
199	1020	Shale & Shells
1020	1075	Shale & Lime Streaks
1075	1260	Lime & Shale
1260	1360	Lime
1360	1610	Lime & Shale
1610	1860	Shale
1860	1990	Shale & Lime
1990	2270	Lime & Shale
2270	2841	Lime & Shale
2841	3167	Lime
3167	3203	Lime & Shale
3203	3315	Lime
	3315	ROTARY TOTAL DEPTH
		D & A

COMMENCED: 12-13-55  
 COMPLETED: 12-24-55

CASING RECORD:

Set 199' 8 5/8" surface casing with 125 sacks cement and 2 % c.c.

STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK    )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Nicklaus #2 located in the SW/4 of the SE/4 of the NW/4 of Section 3, Township 26 South, Range 4 West, Reno County, Kansas.

McKNAB DRILLING, INC.

By   
 Don Gardner

Subscribed and sworn to before me this 4th day of January, 1956.

  
 Notary Public **H E L E N L O N G**  
 STATE COMMISSION

My commission expires November 21, 1956.

JAN 5 - 1956

CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 WELL SEC-3 T-26 R-4W  
 BOOK PAGE 36 LINE 40