

15-155-00138-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 3 Twp. 26 Rge. (E) 4 (W)

Location as "NE/CNW/SW" or footage from lines c. of south 40 acres of SW/4

Lease Owner Stearns Drilling Company

Lease Name Kontz Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 6 19 53

Application for plugging filed November 5 19 53

Application for plugging approved November 5 19 53


Plugging commenced November 6 19 53

Plugging completed November 6 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4245 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	213.36'	None
				5 1/2"	3355.82'	2812.00'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4245 feet to 0 feet for each plug set.

Filed hole with heavy mud to 208'
Set bridging plug at 208'
Placed chat in hole on top of plug to 190'
Ran 5 sacks of cement on top of chat
Let 5 sacks cement set overnight
Ran additional 12 sacks cement
Filled hole with heavy mud to 20'
Set a bridging plug at 20'
Ran 5 sacks cement on top of plug to top of hole

Name of Plugging Contractor Hall & Prather Drilling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
O. G. STEARNS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of November 19 53

[Handwritten Signature] Notary Public.

My commission expires June 20, 1957

24-2678-5 2-52-20M

PLUGGING

FILE SEC 3 T 26 R 40

BOOK PAGE 140 LINE 26

KONTZ # 1

15-155-00138-0000

Operator: Stearns Drilling Company
Contractor: Stearns Drilling Company
Commencement Date: October 8, 1953
Completion Date: October 28, 1953

Location: Center of South 40
Acres of SW/4 of Section 3-26-4
Reno County, Kansas.

Casing Data:

213.36' 8 5/8" Cemented With 175 Sacks.
3355.82' 5 1/2" Cemented With 75 Sacks

WELL LOG

Cellar	0	5
Clay & Red Bed	5	40
Red Bed, Shale & Shells	40	208
Shale & Shells	208	520
Salt & Shale	520	700
Shale	700	735
Lime & Shale	735	2190
Lime	2190	2627
Lime & Shale	2627	2705
Lime	2705	2800
Lime & Shale	2800	2889
Lime	2889	3357
Lime & Shale	3357	3504
Lime	3504	3533
Lime & Shale	3533	3648
Lime	3648	3775
Lime & Chert	3775	4027
Shale	4027	4110
Lime & Shale	4110	4144
Lime	4144	4245
Total Depth:	4245	

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

SUBSCRIBED AND SWORN to before me this 19th day of November, 1953

RECEIVED
NOTARY PUBLIC COMMISSION

NOV 20 1953

COMMERCIAL DIVISION
Notary Public, Kansas

[Signature]
Notary Public

My Commission Expires: June 20, 1957

PLUGGING
FILE SEC 3 T 26 R 40
BOOK PAGE 140 LINE 26