


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Pratt County, Sec. 6 Twp. 27 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Raymond Oil Co., Inc.
Lease Name Beck A#2 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/8/73 19
Plugging completed 10/15/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4251 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	420	none
				5 1/2	4251	3234'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3800' and dumped 5 sacks cement. Loaded hole, shot pipe at 3564', 3475', 3386', 3294', pulled 101 joints. Halliburton pumped 3 sacks hulls, 10 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1973

My commission expires
MARGARET MELCHER
NOTARY PUELIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

Beck #2A

Owner: Cooperative Refinery Association
Contractor: Earl F. Wakefield
Comm: 7-10-51 Comp: 8-1-51

SE NE NW
6-27-12
Pratt County, Kansas
Casing: 420' of 8"
4251' of 5 1/2"

Elevation 1872'

Shale	159
Shale, Sand & Red Bed	630
Shale & Red Bed	1245
Band & Shale	1650
Shale & Shells	1860
Lime	1990
Shale & Shells	2200
Lime & Shale	2405
Lime	2500
Shale	2550
Lime	2640
Sand & Sandy Lime	2710
Lime & Shale	2805
Lime	2915
Lime & Shale	3030
Lime	3115
Lime, Sandy Lime	3215
Lime	3310
Shale	3370
Lime	3479
Sandy Lime	3604
Shale	3629
Shale & Lime	3681
K. C. Lime	3720
Lime	3761
Lime & Sandy Lime	3830
Lime	3945
Lime & Shale	4029
Lime	4104
Viola Chert	4127
Chert & Shale	4149
Lime & Chert	4182
Shale	4195
Sand	4251
Total Depth	4251

4127
1872
2255
4251
1872
2379

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1973
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

I hereby certify that the above is a true and correct copy of the log on the Beck #2A well located SE NE NW 6-27-12, Pratt County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 6th day of August, 1951.

B. James Gaffney

My Commission Expires: 12-23-54