


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 9 Twp. 29S Rge. 6 () (W)  
Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name Graber "A" Well No. #1  
Office Address 706 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 3, 1964 19 64  
Application for plugging filed June 3 19 64  
Application for plugging approved June 3 19 64  
Plugging commenced June 3 19 64  
Plugging completed June 3 19 64  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4475 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 240'  
Bridged hole - plug - 25 sacks cement  
Filled hole to 40'  
plug - 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.  
Address 706 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John E. Brewer (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John E. Brewer  
706 Union Center, Wichita, Kan.  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1964

My commission expires October 9, 1967

Priscilla L. Graham  
Notary Public.

DRILLERS LOG

#1 Graber "A"

LOCATION: C SW NE of Section 9,  
Township 29 South, Range 6 West,  
Kingman County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.  
706 Union Center Building  
Wichita, Kansas

COMMENCED: May 22, 1964

COMPLETED: June 3, 1964

SURFACE CASING: 8-5/8" surface casing set at 237'  
with 200 sacks cement, 1% gel,  
3 sacks calcium chloride, 3 sacks  
ammonia chloride.

ELEVATION: 1544' K. B.  
1541' D. F.  
1539' G. L.

WELL LOG:

0 - 30	Surface clay
30 - 237	Red Bed
237 - 1125	Red Bed & Shale
1125 - 1370	Lime & Shale
1370 - 1530	Shale & Lime
1530 - 2640	Lime & Shale
2640 - 2775	Lime & Shale
2775 - 2950	Shale & Lime
2950 - 3100	Lime
3100 - 3330	Shale & Lime
3330 - 3605	Lime & Shale
3605 - 3890	Lime
3890 - 4065	Shale & Lime
4065 - 4102	Lime
4102 - 4126	Shale & Lime
4126 - 4405	Lime
4405 - 4438	Shale & Lime
4438 - 4475	Lime
4475	Rotary Total Depth D & A


**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Graber "A", as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

  
Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me this 16th day of June, 1964.

My commission expires 10-9-67.

  
Priscilla L. Graham, Notary