

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 175 20403-0000

LEASE NAME Lemert, Mildred

WELL NUMBER 2-34

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 Ft. from N/2 Section Line

1570 Ft. from E. Section Line

SEC. 34 TWP. 32 RGE. 33W (E) or (W)

COUNTY Seward

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P.O. Box 18496, Okla. City, OK 73154-0496

PHONE (405) 848-8000 OPERATORS LICENSE NO. 32334

Date Well Completed 05/79

Character of Well gas

Plugging Commenced 11/21/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/21/00

The plugging proposal was approved on 07/26/00 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2461' Bottom 2473' T.O. 3070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas/Water	0-	2544'	4-1/2"	2552-32'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Pump down 4-1/2" casing, 500# hulls & 130 sx cement, Max PSI 900#, SIP 300#, Pump down backside 8-5/8" w/5 sx. cmt, SI @ 500#, cut off pipe, cap well & clean location

Name of Plugging Contractor Allied Cementing Co., Inc.

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF OK COUNTY OF OK

Randy Gasaway (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Randy Gasaway

(Address) P.O. Box 18496, Okla. City, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 2000

My Commission Expires: 08-31-04

Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION  
License  
DEC 01 2000

CONSERVATION DIVISION  
WICHITA, KS



# ALLIED CEMENTING CO., INC. 5371

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>11/21/00</u>	SEC <u>34</u>	TWP. <u>32s</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>12:25PM</u>	JOB START <u>12:50PM</u>	JOB FINISH <u>1:50PM</u>
LEASE <u>Cement</u>	WELL # <u>2-34</u>	LOCATION <u>Liberal 14N 1E 1/2s E-1s</u>			COUNTY <u>Seward</u>	STATE <u>Ks</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR \_\_\_\_\_ OWNER S.M.C.

TYPE OF JOB O.H.P.

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 4 1/2 DEPTH 2545

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 900 MINIMUM 50

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. 2461-2517

DISPLACEMENT \_\_\_\_\_

CEMENT

AMOUNT ORDERED

225 sks 60/40 + 670 gal 500# C.S. Hulls

Used 135 sks 60/40 + 670 gal 500# C.S. H

COMMON	<u>81</u>	@	<u>7.55</u>	<u>611.55</u>
POZMIX	<u>54</u>	@	<u>3.25</u>	<u>175.50</u>
GFI.	<u>7 sks</u>	@	<u>9.50</u>	<u>66.50</u>
CHLORIDE		@		
<u>C.S. Hulls</u>	<u>5 sks</u>	@	<u>15.50</u>	<u>77.50</u>
		@		
		@		
		@		
		@		
HANDLING	<u>242 sks</u>	@	<u>1.05</u>	<u>254.10</u>
MILEAGE	<u>272 sks</u>	<u>20mi</u>		<u>193.60</u>
				TOTAL <u>1378.75</u>

### EQUIPMENT

PUMP TRUCK CEMENTER Terry Max

# 191 HELPER Wayne

BULK TRUCK

# 280 DRIVER David

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

### REMARKS:

Plug Down CSG with 500# C.S. Hulls +  
130 sks C.M.T. Pressure to 900 P.S.I. SHUT  
IN @ 300 P.S.I. Hookup to ANN Pump  
5 sks C.M.T. Pressure to 500 P.S.I. SHUT  
IN

### SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 225.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 20mi @ 3.00 60.00

PLUG \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 285.00

CHARGE TO: Chesapeake Operating

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 01 2000 FLOAT EQUIPMENT

CONSERVATION DIVISION \_\_\_\_\_ @ \_\_\_\_\_

WICHITA, KS \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Dennis Driel

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME