

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-10059-0000

LEASE NAME LEMERT GAS UNIT "A"

WELL NUMBER 2

1320 Ft. from S Section Line

1320 Ft. from <sup>W</sup> Section Line

SEC. 33 TWP. 32 RGE. 33 (E) or (W)

COUNTY SEWARD

Date Well Completed 8-6-63

Plugging Commenced \_\_\_\_\_

Plugging Completed 11-15-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS P.O. Box 3092 Room 3, 200, Houston, TX 77253

PHONE# (281) 366-7816 OPERATORS LICENSE NO. 5952

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-14-00 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2492' Bottom 2540' T.O. 2630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	<u>SURFACE</u>			<u>8 5/8"</u>	<u>577'</u>	<u>0'</u>
	<u>PRODUCTION</u>			<u>4 1/2</u>	<u>2625'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

WELL PLUGGED 11-15-00. PROCEDURE APPROVED BY KEVIN STRUBE W/KCC. ON 11-6-00. WITNESSED BY STEVE MIDDLETON W/KCC. SET CIBP @ 2450' ON 11-15-00. DUMP 2 SKS CEMENT, PERF SQUEEZE HOLE @ 600' ON 11-15-00. PUMP 9 BBLs CEMENT / 25 SKS IN 4 1/2" CASING @ 800 PSI - 27 BBLs

(If additional description is necessary, use BACK of this form.) OVER

Name of Plugging Contractor HALLIBURTON License No. 5287

Address \_\_\_\_\_ KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company


STATE OF Texas COUNTY OF Harris, ss. JAN 08 2001

Lou Barry (Employee of Operator Amoco Production Company)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Lou Barry

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of December, 192000



Nikki R. Macres  
Notary Public

My Commission Expires \_\_\_\_\_



CEMENT / 75 SKS IN  $4\frac{1}{2}$  X  $8\frac{5}{8}$  ANNULUS 80 PSI

TOTAL CEMENT 100 SKS