


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Seward County, Sec. 32 Twp. 32S Rge. 1 (E) 33 (W)
Location as "NE/CNW/SW" or footage from lines 1320' FEL, 2310' FNL
Lease Owner GULF OIL CORP.
Lease Name FISCHER "A" Well No. 1
Office Address Box 12116, Oklahoma City, OK 73112
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 9-6-1972
Application for plugging filed 9-7-1972
Application for plugging approved 9-6-1972
Plugging commenced 9-7-1972
Plugging completed 9-7-1972
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well EDGAR EVES
Producing formation NONE Depth to top _____ Bottom _____ Total Depth of Well 6450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Chester Lm</u>	<u>dry</u>	<u>5811</u>	<u>5931</u>	<u>8 5/8</u>	<u>1608</u>	<u>—</u>
<u>St. Louis Sd</u>	<u>dry</u>	<u>6389</u>	<u>6418</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 35 sax cement plug 1100-1200', 16 sax cement with 2 sax hulls in top of 8 5/8" SURFACE CASING 45' to 3' below GL. Filled Rat hole with 5 sax cement & Mouse hole with 5 sax cement. Mud wt. 8.9#

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1972

CONSERVATION DIVISION
Wichita, Kansas

9-14-1972

Name of Plugging Contractor HOWCO (If additional description is necessary, use BACK of this sheet)
Address _____

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Fennell Jr.
Box 12116, Oklahoma City, OK 73112
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of Sept, 1972

My commission expires Sept. 3, 1973

J. A. Cantrell
Notary Public.

WELL LOG

Fischer "A" No. 1

Red bed, sd, anhy	0 - 1475'
red beds, anhy	1475 - 1610'
anhy	1610 - 2300'
anhy & lm	2300 - 2940'
lm & sh	2940 - 5665'
sd	5665 - 5790'
lm	5790 - 6450'

TOTAL DEPTH - 6450'

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1972
CONSERVATION DIVISION
Wichita, Kansas