

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-15120395-0000

LEASE NAME Fincham

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
 100' SE of

NW-NW-SE ~~XXXXXXXXXXXXXXXXXXXX~~ Line

_____ Ft. from E Section Line

SEC. 25 TWP. 27S RGE. 12 ~~XXXX~~ (W)

COUNTY Pratt

LEASE OPERATOR Hummon Oil Co

ADDRESS One Main Place, Suite 400, Wichita, KS 67202

PHONE# (316) 263-8521 OPERATORS LICENSE NO. 5050

Date Well Completed 7/14/77

Character of Well Gas

Plugging Commenced 7/10/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

11:30 - 100 shot

Plugging Completed 7/16/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12 3/4	151	None
				5 1/2	4342	2324

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Sand from 4315 to 3800, 5sx cement with dump bailer from 3800 to 3770, pump in 3sx hulls
15sx jell, 50sx cement, 10sx jell, 1sx hull, 180sx cement
60-40 POZ 6% Jell

E. Morgenstern on location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CAREN J. McCULLOUGH
 NOTARY PUBLIC
 STATE OF KANSAS

(Signature) Elmo Morgenstern

(Address) _____

My Appt. Exp. June 29, 1987 SUBSCRIBED AND SWORN TO before me this 17 day of July, 19 85

RECEIVED
 STATE CORPORATION COMMISSION

Caren J. McCullough
 Notary Public

My Commission Expires: June 29, 1987

CONSERVATION DIVISION
 Wichita, Kansas

7-22-1985

Huffman Oil Company - Fincham #1
NW NW SE Sec. 25-27S-12W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
301 S. Broadway
Wichita, Kansas 67202

Commenced: July 2, 1977
Completed: July 14, 1977

Drillers Log

Sand	157
Red Bed	825
Shale & Shells	1364
Anhydrite	1371
Shale & Salt	1625
Shale & Lime Streaks	1805
Shale Shells	2100
Shale	2315
Shale & Lime	2550
Shale	2578
Lime Shale	2775
Shale & Lime	2830
Shale Shells	3040
Shale & Lime	3444
Lime	3620
Lime & Shale	3650
Lime	3790
Lime & Shale	3880
Lime	4015
Lime & Shale	4100
Lime	4180
Lime & Shale	4255
Lime	4355 RTD

RECEIVED
STATE CORPORATION COMMISSION

III 03 1985

CONSERVATION DIVISION
Wichita, Kansas