

1 070239

290(105) R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,591-0000
SE NE NE, SEC. 4, T 27 S, R 12 W/R

TECHNICIAN'S PLUGGING REPORT

4750 feet from S section line
470 feet from E section line

Operator License # 9582

Lease Name Miskimen Well # A-1

Operator: Studer Oil Company
Name & Address Box 925
Pratt, KS 67124

County Pratt 148.69
Well Total Depth 4575 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 3:20 p.m. Day: 29 Month: 4 Year: 1987

Plugging proposal received from Scott Mason

(company name) Studer Oil Company (phone) 316-672-7571

were: 5 1/2" at 4490' PBD 4485' Perfs at 4186-4205'

1st plug sand back to 4130' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 29 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Recovered 1720' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1987

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Paul Luthi
(TECHNICIAN)
CONSERVATION DIVISION
WICHITA, KANSAS

DATE 5-7-87
INV. NO. 16812