

To: 1 040673 7-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202 15-151-10189-0000

API NUMBER 15- Drilled 12/15/54 289 R
W/2 SE NW, SEC. 6, T. 27 S, R. 12 W/EX
3300 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5030
Operator: Vess-TRANS-PACIFIC-OPERATING Co
Name & Address P.O. Box 781350
Wichita, KS 67278

Lease Name McFadden Well # C-8
County Pratt 139.03
Well Total Depth 4278 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 2:45 p.m. Day: 30 Month: 7 Year: 19 92

Plugging proposal received from Monte Andrews
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4273' w/100 sx cement, PBTD 4270', Perfs at 4240-45' (squeezed w/100 sx),
4246-63', 4263-66'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 100 sx cement at 2000',
3rd plug pump 50 sx cement at 750', 4th plug pump 50 sx cement at 435', 5th plug pump 10 sx
cement at 40'. Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 7 p.m. Day: 30 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand
bridge through bailer,
2nd plug (spotted plugs through casing) at 2000' with 100 sx cement,
3rd plug at 750' with 50 sx cement,
4th plug at 460' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2023' of 5 1/2" casing. AUG 4 1992
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my successors) observe this plugging.

DATE 8-12-92
DIV. NO. 35961

Signed Stephen J. Tolson (TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION
CONSERVATION DIVISION Wichita, Kansas
FORM CP-2/3 Rev 01-84