

1 040036
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-29-87 15-151-10186-0000
API NUMBER 15-Drill Completion Date 2/19/52
NW NE NW SEC. 6, T 27 S, R 12 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5087
Operator: Texas Energies, Inc.
Name & Address: P.O. Box 947
Pratt, KS 67124

4950 feet from S section line
3630 feet from E section line
Lease Name McFadden "C" Well # 4
County Pratt 140.86
Well Total Depth 4334 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5 p.m. Day: 29 Month: 12 Year: 19 87

Plugging proposal received from Ted Moff

(company name) Kelso Casing Pulling (phone) 316-672-7838

were: 5 1/2" at 4325' PBSD 4310' Perfs at 4242-68, 3769-71, 3717-19, 3698-3700, 4068-72,
4058-61, 4051-53, 4038-40' (plug at 4214')

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 29 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement,

100 lbs. hulls, and 100 sx cement.

Maximum pressure 100 psi and shut in 0 psi. On vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 1-11-88

INV. NO. 19511

Signed Stephan J. Plifer (TECHNICIAN)

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
JAN 06 1988
1-6-88