

12-29-87

1 040035

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 4/4/52

NE SE NW, SEC. 6, T 27 S, R 12 W/E  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name McFadden "C" Well # 5

Operator: Texas Energies, Inc.

County Pratt 140.24

Name & Address P.O. Box 947

Well Total Depth 4315 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 468

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:50 p.m. Day: 29 Month: 12 Year: 19 87

Plugging proposal received from Ted Moff

(company name) Kelso Casing Pulling (phone) 316-672-7838

were: 5 1/2" at 4302' PBTD 4290' Perfs at 4226-36, 4246-59, 3962-68, (CIBP at 4200' w/1 sx cem.  
1st plug sand back to 3910' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:15 p.m. Day: 29 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3910' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
1-6-88  
JAN 06 1988

Maximum pressure 450 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2600' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-11-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 19513