

To: 1 040686 8-6
STATE CORPORATION COMMISSION
OBSERVATION DIVISION - PLUGGING SECTION
100 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202
TECHNICIAN'S PLUGGING REPORT
15-151-10178-0001

API NUMBER 15- Completion date 7/12/52 1992
NE NE NW, SEC. 6, T. 27 S, R 12 W/E
4950 feet from S section line
2970 feet from E section line

Operator License # 5030
Operator: Vess-Transpacific Operating Co
Name & Address: P.O. Box 781350
Wichita, KS 67278

Lease Name McFadden Well # C-6
County Pratt 138.84
Well Total Depth 4272 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 462

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 p.m. Day: 6 Month: 8 Year: 19 92

Plugging proposal received from Monte Andrews
(company name) Kelso (phone) 316-938-2943

were: 5 1/2" at 4272' w/175 sx cement, PBDT 4140', Perfs at 3718-4157' (8 sets)
1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 750' through tubing,
3rd plug pump 50' sx cement at 490',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 6 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand
bridge through bailer, spotted plugs through 5 1/2" casing:
2nd plug at 750' with 50 sx cement,
3rd plug at 490' with 50 sx cement,
4th plug at 40' with 10 sx cement,
Gel spacer was run between plugs.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 8-20-92
INV. NO. 36006

8-13-92
RECEIVED STATE CORPORATION COMMISSION
OBSERVATION DIVISION WICHITA, KANSAS
Signed [Signature] (TECHNICIAN)