

15-15-10177-0001

268 R

1 010088

API NUMBER 15- Comp. 6-13-51

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 6, T 27 S, R 12 W/EX

990 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Beck "B" Well # 4

Operator: Raymond Oil Company, Inc.
Name & Address: One Main Place, Suite 900
Wichita, KS 67202

County Pratt 137.87

Well Total Depth 4242' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:45 pm Day: 14 Month: February Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

Perfs: 5 1/2" at 4221' PBD 4150' Perfs at 3928-34'; 3878-84'; 3844-48'; 3784-88; 2524'

1st plug sand back to 2470' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 14 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 2470' and dump 5 sx cement on top of sand through bailer. 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi

Remarks: Recovered 2100' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 26 1986

INV. NO. 12690

observe this plugging STATE CORPORATION COMMISSION

FEB 24 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed

Paul A. Luthi (TECHNICIAN)