

1 040440

T6:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion 3/28/51

SE SE SW, SEC. 6, T 27 S, R 12 W/E

660 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9882

Lease Name Beck Well # B-2

Operator: Leasing & Development, Inc.

County Pratt 138.73

Name & Address
120 S. Market, #150
Wichita, KS 67202

Well Total Depth 4268.5 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 18 Month: 7 Year: 19 90

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-4938-2943

were: 5 1/2" at 4218.5' w/175 sx cement, PBTD 2600', Perfs at 2516-20', Elevation 1874' D.F.
1st plug sand back to 2465' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 18 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 4 1/2" liner from 2190-2600', cemented with 150 sx

1st plug sanded back to 2465' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1815' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 7-30-90

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 28818

7-18 SEP 14 1990