

10-21

2 070112

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 095-97,916 C-8651  
SE , SEC. 19 , T 27 S, R <sup>10</sup> W/EX  
1650 feet from N/S section line  
440 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Miles Well # B-6 SWD

Operator: Texaco Producing, Inc.

County Kingman 113.88

Name & Address P.O. Box 3420 P.O. Box 779

Well Total Depth 3504 feet

Tulsa, OK 74102 Kingfisher, OK 73750

Conductor Pipe: Size feet

Surface Casing: Size 12-1/2" feet 317

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Texaco License Number 4742

Address

Company to plug at: Hour: 8:30 Day: 21 Month: 10 Year: 19 88

Plugging proposal received from T. C. Williams

(company name) Texaco (phone) 918-560-6000

were: Sand bottom - 10 sx of common - 50' below surface to surface

Fill back side

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by John Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 4:30 Day: 21 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Sanded bottom to 3415' - ran 10 sx common w/bailer - ran tubing to 2512' - pumped 10 sx sur-fill - pulled tubing to 2007' - pumped 200# hulls, 10 sx of sur-fill - pulled tubing to 1504' - pumped 70 sx sur-fill & 75 sx 60/40 - ran tubing to 1914' - pumped 500# hulls, 295 sx 60/40 - got no return - ran tubing to 1192' - pumped 500# hulls, 200 sx sur-fill - no return - ran tubing to 1034' - pumped 200# hulls & 300 sx 60/40 - no return - taged cement at 745' - pumped 115 sx 60/40 poz - got return to surface - pulled tubing filled to surface with 10 sx 60/40 poz - tied to back side - pumped 500# hulls, 325 sx 60/40 poz - Max Press was 450# - shut in was 450# - pumped by

B.J. Titan #422360.

Remarks:

INVOICED (If additional description is necessary, use BACK of this form.)  
(did / did not) observe this plugging.

DATE 11-7-88

Signed [Signature] (TECHNICIAN)

INV. NO. 22916

NOV 15 1988

JAN 25 1989

FORM CP-2/3