

TECHNICIAN'S PLUGGING REPORT

Operator License # 6120

Operator: Cabot Petroleum Corporation  
Name & Address: 9400 N. Broadway, Ste. 608  
Oklahoma City, OK 73114

1320 feet from S section line

3660 feet from E section line

Lease Name Naden Well # 2-29

County Seward

Well Total Depth 2825 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cabot Petroleum Corporation License Number 6120

Address 9400 N. Broadway, Ste. 608, Oklahoma City, OK 73114

Company to plug at: Hour: 8 a.m. Day: 7 Month: 4 Year: 19 92

Plugging proposal received from Carl Cowan

(company name) Cabot Petroleum Corp. (phone) 405-478-6514

were: 4 1/2" at 2823' w/600 sx cement, PBD 2784', Perfs at 2532-38, 2560-74, 2597-2609, 2648-58

1st plug set CIBP at 2460' with 2 sx cement on top with bailer,

2nd plug circulate hole with mud and pump 20 sx cement at 1700',

3rd plug pump 20 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 7 Month: 4 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2460' with 2 sx cement on top with bailer,

2nd plug circulated hole with mud, pumped 20 sx cement at 1700',

3rd plug pumped 20 sx cement at 700',

4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix by Halliburton. No casing recovery.

If additional description is necessary, use BACK of this form.)

I (did / ) serve this plugging.

Signed Glenn P. Barlow (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
MAY 31 1995