

To: 100151
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

8-27

API NUMBER 15-175-21,395-0005
NW SW, SEC. 36, T 32 S, R 33 ~~WXX~~
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606

Lease Name Oxy-LB Well # I-36

Operator: Murfin Drilling Company, Inc.

County Seward 194.42

Name & Address 250 N. Water, Ste. 300

Well Total Depth 5982 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1535

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Quality Well Service License Number 31925

Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 8:30 a.m. Day: 27 Month: 8 Year: 19 97

Plugging proposal received from Richard McIntyre

(company name) Quality Well Service (phone) 316-278-2476

logs: 5 1/2" at 5956' w/330 sx cement, PBTD 5915', Perfs at 4652-54, 4719-22, 5762-66'

1st plug pump 2 sx hulls and cement to surface,

Check backside.

9-4-97

RECEIVED
KANSAS CORP
1997 SEP 11 12:35

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 27 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug displaced 50 sx cement with 200 lbs. hulls to 4600' (8/15/97)

2nd plug pumped 100 sx cement and displaced to 3000',

3rd plug pumped 50 sx cement and displaced to 1560',

4th plug pumped 50 sx cement and displaced to 700',

5th plug pumped 10 sx cement at 40-0'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2613' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE: 9-8-97

Signed Gary Wentzel
(TECHNICIAN)

INV. NO. 48929