

To: 1 020448 4-8  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-21,175-0000 94R

C. NE, SEC. 30, T. 32 S, R. 33 W/E

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6120

Lease Name Luft Well # 2-30

Operator: Cabot Oil & Gas Corporation

County Seward

Name & Address 9400 N. Broadway, Suite 608

Well Total Depth 2850 92.62 feet

Oklahoma City, OK 73114

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 672

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cabot Oil & Gas Corp. License Number 6120

Address 9400 N. Broadway, Ste. 608, Oklahoma City, OK 73114

Company to plug at: Hour: 8 a.m. Day: 8 Month: 4 Year: 19 92

Plugging proposal received from Carl Cowan

(company name) Cabot Oil & Gas Corp. (phone) 405-478-6523

were: 4 1/2" at 2849' w/360 sx cement, PBD 2759', Perfs at 2457-2661'

1st plug set CIBP at 2500' with 1 sx cement on top,

2nd plug pump 20 sx cement at 1700-1465',

3rd plug pump 20 sx cement at 700-465',

4th plug pump 4 sx cement at 50 to-3'.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 8 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2400' with 2 sx cement on top with bailer,

2nd plug ran tubing, circulated hole with mud, spotted 20 sx cement at 1715', displaced w/mud,

3rd plug pumped 20 sx cement at 702', displaced with mud,

4th plug pulled tubing and filled to surface.

Remarks: Used 60/40 Pozmix by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(old instructions) observe this plugging.

DATE 4-28-92

Signed Glenn B. Barlow (TECHNICIAN)

INV. NO. 35080

STATE RECEIVED  
APR 14 1992  
CONSERVATION DIVISION  
Wichita, Kansas