

To: 1 020447  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-9

API NUMBER 15-175-21,221-0000 95P

W/2 SW, SEC. 30, 'T. 32 S, R 33 W/EX  
1320 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6120

Lease Name Luft Well # 3-30

Operator: Cabot Oil & Gas Corporation  
Name & Address 9400 N. Broadway, Suite 608  
Oklahoma City, OK 73114

County Seward

Well Total Depth 6350 206.37 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1630

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cabot Oil & Gas Corp. License Number 6120

Address 9400 S. Broadway, Ste. 608, Oklahoma City, OK 73114

Company to plug at: Hour: 8 a.m. Day: 9 Month: 4 Year: 1992

Plugging proposal received from Carl Cowan

(company name) Cabot (phone) 405-478-6514

were: 4 1/2" at 6003' w/400 sx cement, PBD 5880', Perfs at 2559-64, 2586-94', TOC 2400'

1st plug set CIBP at 2500', 2850', 5716', 2 sx on top,

2nd plug load hole with mud and pump 50 sx cement at 1650',

3rd plug pump 50 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 9 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500', 2850', 5716' with 2 sx cement on top,

2nd plug loaded hole with mud and pumped 50 sx cement at 1650',

3rd plug pumped 50 sx cement at 700',

4th plug pumped 10 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1992  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix by Halliburton. Recovered 2360' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If possible, ~~operator~~ observe this plugging.

DATE 3-28-92

Signed Glenn R Barlow  
(TECHNICIAN)

INV. NO. 35078