

RECEIVED  
KANSAS CORPORATION COMMISSION

9-30

2-010016

19  
R

OCT 8 1992

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-095-21,279-0000

SE SW NW, SECTION 9 TOWNSHIP 29 RANGE 6W

OPERATOR LICENSE # 5097

3195 FEET FROM S SECTION LINE  
4515 FEET FROM E SECTION LINE

OPERATOR Martin Oil Producers  
NAME & 150 N. Main, #1010  
ADDRESS Wichita, KS 67202

LEASE NAME: Graber-Pinkerton #2

COUNTY: Kingman

WELL TOTAL DEPTH: 4120' 133.90

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 254'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: P. O. Box 347, Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 30 MONTH: 9 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: William Stockstill  
COMPANY NAME: Martin Oil Producers PHONE: 316-264-0352

WERE: Set 4-1/2" bridge plug @ 4066' - sand to 4016' & top  
w/4 sx cmt - 4-1/2" csg @ 4016' - shoot pipe off & spot  
35 sx cmt @ 805' - open hole 4109-4120' - 35 sx cmt @  
445' & circ cmt from 305' to surf.

PLUGGING PROPOSAL RECEIVED BY: Dave Wertz

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 11:30 DAY: 30 MONTH: 9 YEAR: 1992

ACTUAL PLUGGING REPORT:

Set 4-1/2" bridge plug @ 4066' - sanded to 4016' &  
topped w/4 sx cmt - shot pipe off @ 2400' - pulled pipe  
and spotted 35 sx cmt @ 805' - circ 135 sx cmt from  
445' to surf - retrieved 2400' of 4-1/2" csg.

REMARKS: Used 60/40 poz 4% gel - Allied #3105

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 10-20-92

INV. NO. 36509

15/

Michael R. Wilson (AGENT)