

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20403-00-00
Spot: CNE Sec/Twnshp/Rge: 34-32S-33W
1320 feet from N Section Line, 1570 feet from W Section Line
Lease/Unit Name: MILDRED LEMERT Well Number: 2
County: SEWARD Total Vertical Depth: 2545 feet

Operator License No.: 32334 Conductor Pipe: Size 20 feet: 40
Operator Name: CHESAPEAKE OPERATING, INC. Surface Casing: Size 8.625 feet: 608 WITH 550 SX CMT
Address: PO BOX 18496 Production: Size 4.5 feet: 2544 WITH 650 SX CMT
OKLAHOMA CITY, OK 73154 11/21 Liner: Size feet: 82.71

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/21/2000 12:50 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE Phone: (405) 848-8000

Proposed Plugging Method: PUMP 500# HULLS. FILL CASING WITH 60/40 POZMIX 6% GEL TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2000 2:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2461-63, 2469-71, 2498-2502, 2504-10, 2515-17. PUMPED DOWN 4 1/2" CASING 500# HULLS AND 130 SX CMT. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CMT. SHUT IN AT 500#.

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE 12/11/00
INV. NO. 2001061096

NOV 27 2000

Form C-23

MP