

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,679-0000 LR

S14/514, Sec. 34, T32 S, R33 W/2

660 feet from 2/5 section line

660 feet from W/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License 05760

Lease Name Lemerit Well # 1

Operator: Drex Corp
Name & Address 1670 Broadway, Suite 3301
Denver, Colo., 80202

County Leward

Well Total Depth 6400 feet 2081

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1519

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union Center, Wichita Kansas 67202

Company to plug at: Hour: 6:00 PM, Day: 16 Month: March Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Small

(company name) Murfin Drilling Co. (phone) _____

were: 1st plug @ 1560' w/ 50 sbp cement. 2nd plug @ 660'
w/ 25 sbp cement. 3rd plug on solid bridge @ 40' w/ 10 sbp cement
filling hole to 0'. Circulate 10 sbp cement, in each the
rat & mouse hole. Plugged the water well w/ 5 sbp
cement & cement inside & around out side of top of well Halliburton
accomplished the plugging.

Signed Paul A. Luthis
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ☒

Operations Completed: Hour: 8:40 PM, Day: 16 Month: March Year: 1983

ACTUAL PLUGGING REPORT This hole was plugged as orders
given in above paragraph.

Remarks: Cement used w/ 50/50 ppg w/ 4 1/2 gal 3% CC.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) / did not) observe this plugging.

INVOICED

DATE 4-8-83

INV. NO. 3918-W

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthis
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82