

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-10059-00-00  
Spot: CNW Sec/Twnshp/Rge: 33-32S-33W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease/Unit Name: LEMERT GAS UNIT "A" Well Number: 2  
County: SEWARD Total Vertical Depth: 2630 feet

Operator License No.: 5952 Conductor Pipe: Size \_\_\_\_\_ feet:  
Operator Name: AMOCO PRODUCTION COMPANY Surface Casing: Size 8.625 feet: 577 WITH 650 SX CMT  
Address: 2225 WEST OKLAHOMA AVENUE Production: Size 4.5 feet: 2624 WITH 1000 SX CMT  
ULYSSES, KS 67880 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_ 85.48

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2000 11:15 AM  
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES  
Proposal Rcvd. from: SPANKY Company: AMOCO Phone: (316) 356-6955

Proposed Plugging Method: CIBP @ 2450' WITH 2 SX CMT. PERFORATE AT 600'. CIRCULATE CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/15/2000 12:20 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:  
PERFS AT 2492-2500'. SET CIBP @ 2450' WITH 2 SX CMT ON TOP. PERFORATE CASING AT 600'. PUMP IN 45 BBL WATER AT 800 PSI. CHANGED TO CEMENT. PUMP IN 100 SX CMT AT 850 PSI 1.5 BBL PER MINUTE. CIRCULATED CEMENT TO TANK.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 27 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.  
Plugged through: CSG

District: 01 Signed \_\_\_\_\_ (TECHNICIAN)

INVOICED  
DATE 11/28/00 NOV 20 2000  
INV. NO. 2001061012 MP  
FORM CP-273