

1090372

API NUMBER 15- 151-20,395-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

100' SE NW NW, SEC. 25, T 27 S, R 12 (W/R)

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Fincham Well # 1

Operator: Hummon Corporation

County Pratt 141.54

Name & Address 400 One Main Place

Well Total Depth 4355 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 12 3/4 feet 151

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 15 Month: July Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 4348' PBTD 4315' Perfs at 3891-95'; 3856-58'; 4254-60'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls

and 180 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 am Day: 15 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 180 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 22 1985

Maximum pressure 100 psi and shut in 1000 psi CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 2324' 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

INVOICED

DATE 7-24-85

Signed R. B. Barlow (TECHNICIAN)

INV. NO. 9095