

1030524

API NUMBER 15- 151-20,704-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NE , SEC. 25 , T 27 S , R 12 (W) E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Barnes Well # 1-25

Operator: Texas Energies, Inc.

County Pratt 143.33

Name & Address P. O. Box 947

Well Total Depth 4410 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 219

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 17 Month: September Year: 19 85

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4409' PBD 4347 Perfs at 3955-58; 4020-22; 4012-14' 4285-4290; 4074-94'
1st plug sand back to 3905' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 10 3/4" rubber plug and pump 180 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 17 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3905' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10
sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 180 sx cement.

Maximum pressure 400 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton Recovered 2015' 4 1/2" casing. RECEIVED
(If additional description is necessary, use BACK of this form.) STATE CORPORATION COMMISS

observe this plugging.

INVOICED

Signed Steve Stewart
(TECHNICIAN)

SEP 23 1985

DATE SEP 25 1985

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 10262

FORM CP-2/3
Rev. 01-84