

1041389

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151-21,138-0000
W/2 W/2 NE SEC. 25, T 27 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARNES SWD WELL # 2-25

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT 147.32

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 4533 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4480' WITH 175 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 622' WITH 300 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG : SIZE 16" @ 96' WITH 100 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL ~~XXXXXXXXXX~~ D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 847 PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 9:15 AM DAY: 29 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ALAN DICK

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS 4106-4109. SQUEEZED OPEN HOLE 4480-4533

SET CIBP @ 4200' AND 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED DOWN 8 5/8"

SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8"

WIPER PLUG & 100 SX CEMENT. MAXIMUM PRESSURE AT 150#. SHUT IN WITH 100#.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 29 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

SET CIBP @ 4200' AND 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED DOWN 8 5/8"

SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8"

WIPER PLUG & 100 SX CEMENT. MAXIMUM PRESSURE AT 150#. SHUT IN WITH 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1810' OF 5 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING DATE 3/15/00 SIGNED Stephen J. Pfafer (TECHNICIAN)

INVOICED
DATE 3/15/00
FILE NO. 06/426

RECEIVED

STATE CORPORATION COMMISSION

MAR 14 2000

CONSERVATION DIVISION
Wichita, Kansas