

1 010274

8-7-87 15-151-30192-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

NW SE NW, SEC. 25, T 27 S, R 12 W/E
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Barnes Estate Well # 2

Operator: Bowers Drilling Company Inc.
Name & Address: 125 North Market, Suite 1425
Wichita, KS 67202

County: Pratt 145.70

Well Total Depth 4483 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 803

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bowers Drilling Company Inc. License Number 5435

Address 125 North Market, Suite 1425, Wichita, KS 67202

Company to plug at: Hour: 11:40 a.m. Day: 7 Month: 8 Year: 19 87

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Company Inc. (phone) 316-886-5520

were: 4 1/2" at 4480' PBTD 4423' Perfs at 4288-92, 4358-61'

1st plug sand back to 4200' and dump 4 sx cement on top of sand with bailer,

2nd plug pump 3 sx hulls, 110 sx thrifty mix with 2 sx hulls mixed in.

Plugging Proposal Received by Don Ubel & Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:05 p.m. Day: 7 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 110 sx of thrifty mix with 2 sx hulls mixed in. RECEIVED STATE CORPORATION COMMISSION

8-11-87 AUG 11 1987

Maximum pressure 500 psi and shut in 400 psi. CONSERVATION DIVISION Wichita, Kansas

Remarks: Used Thrifty Mix by B.J. Titan. Recovered 1260' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (Stamp) observe this plugging.

DATE 8-12-87

Signed Jack Luthi (TECHNICIAN)

INV. NO. 17796