

6060031

15-167-21916-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

SW, Sec. 10, T 15 S, R 13 W

330 feet from ~~W~~ S section line

1980 feet from W ~~S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5726

Lease Name Hartman Winter Well # 1

Operator: Driscoll Lease Operations, Inc.  
Name & Address: Box 226, Russell, Ks. 67665

County Russell

Well Total Depth 3360 feet \$109.20

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 528

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated, \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 3:00PM Day: 28 Month: 9 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mallard Kelso

(company name) Kelso Casing Pulling (phone) 716-938-2457

were: Order 165 sh. 50 permix - 4% Gel - 3% Gel. U., 15 sh. Gel., 5 sh. hulls & 8 5/8" plug.

Signed *[Signature]*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15PM Day: 28 Month: 9 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 528' w/ 275 sh. 5 1/2" set at 3359' w/ 250 sh. Top perf. 2980'. ~~Set~~ Plug bottom w/ 5 sh. cement, sand & 5 sh. cement to 3250' shot pipe 3 times & Recovered 1735'. Pumped in 8 5/8", 4 sh. hulls, 25 sh. cement, 10 sh. Gel, 40 sh. cement, 5 sh. Gel, 1 sh. hulls, released plug & followed w/ 100 sh. w/ 650 pounds pressure.

Remarks: By Allied Cementing Co.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED RECEIVED  
STATE CORPORATION COMMISSION  
DATE 10-11-83  
INV. NO. 5769-0  
10-11-83  
CONSERVATION DIVISION  
Wichita, Kansas

Signed *[Signature]*  
(TECHNICIAN)