

1 030873

10-12-87

15-097-30014-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA
C SE NE, SEC. 29, T 27 S, R 20 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144
Operator: Mull Drilling Company
Name &
Address P.O. Box 2758
Wichita, KS 67201

Lease Name Bissitt "A" Well # 1
County Kiowa 159.80
Well Total Depth 4917 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 550

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 12 Month: 10 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4914' Perfs at 4894-4900'

1st plug sand back to 4840' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement. (Gel circulated outside surface pipe.)

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 12:45 p.m. Day: 12 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4840' and dumped 4 sx cement on top thru bailer,
2nd plug spot through tubing at 780' with 50 sx cement,

3rd plug spot through tubing at 570' with 50 sx cement,

4th plug spot through tubing at 40-0' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix by Allied. Recovered 820' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-20-87

INV. NO. 18578

Signed Steve Lacey
(TECHNICIAN)