

1 060469

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,371-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Operator: Imperial Oil Co.
Name & Address: 720 4th Financial Center
Wichita, KS 67202

4620 feet from S section line
3300 feet from E section line

Lease Name Dean Well # 1-11

County Ford 162.70

Well Total Depth 5006 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 558 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 15 Month: January Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4979' Perfs at 4939-57'

1st plug pump 50 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 125 sx cement

RECEIVED

STATE CORPORATION COMMISSION

JAN 23 1985

CONSERVATION DIVISION

Wichita, Kansas

Plugging Proposal Received by Paul A. Luther
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:55 am Day: 15 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement to bottom, 2nd plug squeezed

well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped an additional 125 sx cement.

Maximum pressure 1000 psi and shut in 5-0 psi

Remarks: Recovered 1971' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

(additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 1-28-85

Signed Paul A. Luther
(TECHNICIAN)

INV. NO. 6653