

1
040468

API NUMBER 15- 057-20,341-000 *PR*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SE SW, SEC. 2, T 27 S, R 22 W/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028
Operator: Imperial Oil Company
Name & Address: 720 4th Financial Center
Wichita, KS 67202

Lease Name Conley Well # 1-2
County Ford 1102.54
Well Total Depth 5001 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 540

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 15 Month: January Year: 19 85

Plugging proposal received from Mike Gomez
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4990' PBD 4958' Perfs at 4931-34'

1st plug pump 50 sx cement to bottom

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
1-23-85
JAN 23 1985

Plugging Proposal Received by *Paul A. Luther* CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50 pm Day: 15 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement to bottom, 2nd plug squeezed
well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"
rubber plug and pumped an additional 125 sx cement.

Maximum pressure 700 psi and shut in 350 psi

Remarks: Recovered 2120' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton.
(additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 1-28-85

Signed *Paul A. Luther* (TECHNICIAN)

INV NO. 6694