



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 20 1962

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dec. 15, 1962.

Dear Sir:

Mr. George Pine of Messman Rinehart Oil Co. has this date requested permission to plug the following described well:

Mr. George Pine guarantees payment of the plugging fee.

Operator's full Name: Messman Rinehart

Complete Address: 518 Petroleum Bldg. Wichita, Kansas.

Lease Name: Gertrude Cannon #1 Well No. #1

Location: C-SW-SE Sec. 20 Twp. 27S Rge. 10(E) (W)

County Kingman County Total Depth 3060. Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. George Pine was instructed to plug the well as follows:

255' of 10 3/4" surface pipe circulated with cement. Hole filled to 180' with heavy drill mud, 1/2 sack hulls, 1st cementing plug & 25 sacks cement. Hole filled to 40' with heavy drill mud 1/2 sack hulls, 2nd cementing plug & 15 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herman Quinter  
 Conservation Division Agent