

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg., 2nd Floor, Market

WICHITA, KANSAS 67202

RECEIVED
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mallonee- Mahoney has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney

Complete Address: 925 Sutton Place, Wichita, Kansas

Lease Name: Lemert Well No. 1

Location: App C NE Sec. 34 Twp. 32 Rge. 33 (E) (W)

County: Seward Total Depth 2532' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:


5 1/2" to 2532' circulated w/ cement. Top perforations 2443'

Plug bottom w/ 20 sacks cement. Top of cement on 2300'

Mud 2300' to 900' Spot 20 sacks cement 900' to 750'

Mud 750' to 60' Plug, Hulls & 10 sacks cement 60' to 0'.

Very truly yours,


Conservation Division Agent