

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Glover of Cabot Corp. has this

date requested permission to plug the following described well:

Mr. Glover guarantees payment of the plugging fee.Operator's full Name: Cabot CorporationComplete Address: Box 1101, Pampa, TexasLease Name: Fischer Well No. 1-32Location: 1650' FSL & 2310' FWL Sec. 32 Twp. 32 Rge. 33 (E) (W)County: Seward Total Depth 6350' Oil WellGas Well X Input Well SWD Well D & A X Lost Hole Mr. Glover was instructed to plug the well as follows:8 5/8" to 1640' circulated w/ cement. Mud 6350' to 2750'Spot 100 sacks cement 2750' to 2450' Mud 2450' to 1100'Spot 35 sacks cement 1100' to 1000' Mud 1000' to 50'Plug, Hulls & 15 sacks cement 50' to 0'.

Very truly yours,

Conservation Division Agent