

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this
date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Cooper "B" Well No. 1

Location: App C Sec. 25 Twp. 32 Rge. 33 (E) (W)

County: Seward Total Depth 2610' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

8 5/8" to 607' circulated w/ cement. 5 1/2" to 2610' cemented.

Top perforations 2442' Plug bottom w/ 20 sacks cement.

Top of cement. 2320' Mud 2320' to 679'

Spot 15 sacks cement 679' to 574' Mud 574' to 35'

Plug, Hulls & 5 sacks cement 35' to 0'.

Very truly yours,

Conservation Division Agent