

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

11-5-62 NOV 5 1962

Nov. 1, 1962. CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of D. R. Lauck Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Clyde Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Co. Inc.

Complete Address: 301 S. Broadway Wichita, Kansas.

Lease Name: Barnes Estate #1 Well No. #1

Location: NW-SE-NW Sec. 25 Twp. 27S Rge. 12(E) (W) X

County Pratt Total Depth 4482' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clyde Merckle was instructed to plug the well as follows:

~~804' of 8 5/8" surface pipe circulated with cement. Hole filled to 200' with heavy drill mud, 1 sack hulls, 1st cementing plug and 20 sacks cement, Hole filled to 40' with heavy drill mud, 1 sack hulls, 2nd cementing plug and 10 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.~~

Very truly yours,

Herman J. Gustaf
 Conservation Division Agent