

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gale Metz of Rains & Williamson Oil has this date requested permission to plug the following described well:

Mr. Metz guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Bowers Well No. # 1

Location: C NW NW Sec. 23 Twp. 27 Rge. 20 (E)(W) W

County Kiowa Total Depth 4890' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Metz was instructed to plug the well as follows:

554' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 600', 1st cementing plug, bridge with 1/2 sack of hulls on fluid at 600', and cement with 35 sacks. Fill hole with drilling mud to 45', bridge with 1/2 sack of hulls, and cement with 15 sacks to base of cellar.

Very truly yours,

Archie Elving
Conservation Division Agent