

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP B. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

14 January 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Albert Nunch of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: J. Mark Richardson

Complete Address: 640 Century Plaza Bldg. Wichita Kansas 67202

Lease Name: Mc Ladden B Well No. 2

Location: SE-SE-SW Sec. 34 Twp. 27S Rge. 20W (E) (W)

County: Kiowa Total Depth: 4902'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: This well was completed but never produced.

Mr. Nunch was instructed to plug the well as follows:

There is 604' of 8 3/8" surface casing cement circulated with 450 lbs of cement. There was 4901' of 4 1/2" production pipe run & cemented with 150 lbs of cement. They perforated production pipe from 4880' to 4886'. 1st plug & sand off bottom back to 4850' & put 4 lbs of cement on top of sand. 2nd plug they pumped in 5 lbs of hulls, 25 lbs of gell 50 lbs of cement & 8 lbs of gell & then released

Very truly yours,

Paul Luth

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
1-26-82
JAN 26 1982

CONSERVATION DIVISION
Wichita Kansas

(over)

rubber plug and pumped 100 lbs of cement on top of it.
They recovered 3030' of 4 1/2" pipe. The cement used was
50/50 sand 4 3/4" Jell 3 3/4" C.C. The plugging was accomplished
by Halliburton Co. out of Pratt Kans. The well was shut
in at 400 lbs