


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 26 Twp. 29 Rge. 13 E(W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
530' NSL, 330' EWL of SW/4

Lease Owner White Hawk Oil Company  
Lease Name Larrison Well No. 7  
Office Address Box 1150, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Oil  
Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced April 1 19 78  
Plugging completed April 12 19 78  
Reason for abandonment of well or producing formation

Depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well 4606'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1048'	none
				5 1/2"	4588'	3,416.69'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Dumped sand to 4550' and 5 sacks cement.  
Shot casing at 3500' and 3350'.  
Spotted 40 bbls. oil.  
Pulled 108 joints 5 1/2" casing.  
Plugged well with 5 sacks hulls, 25 sacks gel and 150 sacks cement with 2% added gel.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1978 09:14-78

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold

P. O. Box 698, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of April, 1978

My commission expires

ANITA L. BOGLE  
Barton County, Kansas  
My Appt. Exp. 11/21/81

Anita L. Bogle  
Notary Public.

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

LARRISON #7  
 530' N of SL & 330' E of WL  
 SW/4, Sec. 26-29S-13W  
 Pratt County, Kansas

COMMENCED: February 28, 1974  
 COMPLETED: March 11, 1974

OPERATOR: WHITE HAWK OIL COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	145	Sand	Ran 7 jts. of 48# 13-3/4" csg. set @ 195' cemented w/280 sacks Posmix 12-1/2# Gilsomite, 1/4# Floseal per sack, 3% CC. P.D. @ 6:00 PM, February 28, 1974. Cement circulated.
145	230	Redbed	
230	720	Redbed-Shale	
720	1050	Shale	
1050	1745	Shale-Shells	
1745	1875	Shale-Lime	
1875	2505	Lime-Shale	
2505	2950	Shale-Lime	Ran 39 jts. of 28# 8-5/8" csg. set @ 1046' cemented w/500 sacks Howcolite, 100 sacks Posmix, 10# Gilsomite, 1/2# Flo-seal, 3% CC. P.D. @ 5:30 AM, March 2, 1974.
2950	3115	Lime-Shale	
3115	3615	Shale-Lime	
3615	3835	Shale-Sand	
3835	4475	Lime	
4475	4540	Shale-Sand	
4540	4606	Lime	
4606 Total Depth			Ran 149 jts. of used 5-1/2" csg. set @ 4588' cemented w/175 sacks 50/50 Posmix, 2% Gel, 18% Salt, 3/4% CFR-2. P.D. @ 12:00 Noon, March 11, 1974.


I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled 530' N of SL & 330' E of WL, SW/4 of Sec. 26-29S-13W, Pratt County, Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
 JAMES S. SUTTON II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 20th day of March, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



*Marjorie Hall*  
 MARJORIE HALL - NOTARY PUBLIC

Commission Expires: November 29th, 1975.

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 02 1978

STATE CORPORATION COMMISSION  
 Wichita, Kansas