


15.15.0006 - 00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTE



Locate well correctly on above
Section Plat

Pratt County, Sec. 25 Twp. 29 Rge. 13 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE. 1/4, SW. 1/4, SW. 1/4
Lease Owner Harbar Drilling Company
Lease Name Combs Well No. I
Office Address 1019 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Rotary Dry Hole
Date well completed 11/20 19 49
Application for plugging filed 11/21 19 49
Application for plugging approved 11/21 (Verbal) 19 49
Plugging commenced 11/21 19 49
Plugging completed 11/21 19 49
Reason for abandonment of well or producing formation None present
If a producing well is abandoned, date of last production X 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation None present Depth to top X Bottom X Total Depth of Well 4730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface soil	None	0	10'	10 3/4	556'	None
Surface sands & Gravel	Fresh water	10'	100'			
Shale & sand	Dry	100'	560			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole from T. D. (4730) to 250' with heavy rotary mud. Set wooden plug at 250' and dumped 20 sx. cement on top plug. Filled hole with mud from top cement back to 20' where another wooden plug was set and 10 sx. cement was dumped filling top casing and bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Company
Address 1019 Central Bldg., Wichita, Kansas


STATE OF Kansas COUNTY OF Barton, ss.
I Roy Cook (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roy Cook (Address) 1019 Central Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 23rd day of November 19 49.
Notary Public.

My commission expires 9-4-50

22-5133-3 9-48-10M



11-29-49

COMBS NO. 1

SE 1/4 SW 1/4 Sec. 25-298-13W, Pratt County, Kansas

Rigging up Rotary Tools 10-26-49
Tearing down Rotary Tools 11-22-49

Run 14 Jts. 560' 10 3/4" surface casing.
Set at 556' and cemented with 215 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand and shale	0	70
Sand and clay	70	125
Sand and gravel	125	250
Sand and clay	250	510
Shale and shells	510	795
Shale	795	1590
Anhydrite	1590	1945
Shell and shells and lime	1945	2085
Shale and lime	2085	2410
Lime	2410	2580
Lime and shale	2580	2680
Lime and shale broken	2680	2820
Lime and shale	2820	3150
Shale and shells	3150	3315
Lime, broken	3315	3425
Lime and shale	3425	3555
Lime	3555	4360
Shale	4360	4368
Shale and lime	4368	4477
Lime	4477	4480
Lime chert and shale	4480	4535
Lime	4535	4587
Sand	4587	4603
Sand and shale	4603	4617
Lime	4617	4730 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 28th day of November, 1949.

My commission expires: March 22, 1952.

William Kelly

Notary Public

RECEIVED

NOV 29 1949

PLUGGING
FILE SEC 25 T 29 R 13W
BOOK PAGE 176 LINE 10