

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Flora

WELL NUMBER #1

SPOT LOCATION SW-SW-SW

SEC. 24 TWP. 29S RGE. 13 (E) or (W)

COUNTY Pratt

Date Well Completed May-1987

Plugging Commenced 6-16-87

Plugging Completed 7-21-87

LEASE OPERATOR MAR MAC PETROLEUM CO.,

ADDRESS 1026 Union Center Bldg Wichita, Ks. 67202

PHONE (316) 267-6063 OPERATORS LICENSE NO. 9854

Character of Well D&A  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing formation None Depth to top \_\_\_\_\_ bottom T.D. 4715'  
 Show depth and thickness of all water, oil and gas formations. PBID 4225 Perfs: 3936-38 2 shots per foot

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD 99' to top of cement

| Formation | Content | From | To | Size  | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 429'   | 0          |
|           |         |      |    | 5 1/2 | 4285'  | 47 JFS.    |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.


SEE BACK OF PAGE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893  
 Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of/plugging contractor) or  
 (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.



JUL 30 1987  
 (Signature) Judy Berry  
 (Address) Box 847 Pratt, Kansas 67124

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1987

Dorothy M. Furgason  
 Notary Public

My Commission expires: February 6, 1989

*7-28-87  
 added 1/4 yard of  
 cement - filled to  
 top.*

June 16, 1987:

To location, spotted rig, shut down.

June 18, 1987

To location, rigged up. Got bottom hole flag at 4250', dumped 6 bbls. sand in hole, with 30 bbls. of water. Shut down.

June 19, 1987

To location, bottom was 275' from plug. Dumped 5 sx. of cement. rigged up Electra Log, shot casing off 3 times. Shut down.

June 20, 1987

To location, Electra Log shot off casing, got 47 jts. of casing out of well, closed well in, shut down, moved off location.

July 21, 1987

B J Titan finished top hole plugging. ISIP 300#, 4:00 P.M. Top hole plug was 2 hulls, 10 gel, 50 cement, 10 gel, 1 sx. hulls, plug, 130 sx. cement. 60-40 poz, 6% gel.

