


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 24 Twp. 29 Rge. 13 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines G-SE SW  
Lease Owner Frontier Oil Co.  
Lease Name Flora Well No. L  
Office Address 580 Fourth Natl. Bldg. Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Dec. 17, 19 61  
Application for plugging approved Dec. 17, 19 61  
Plugging commenced Dec. 17, 19 61  
Plugging completed Dec. 27, 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_  
No longer a producer  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	960'	none
				5 1/2	4345'	3516'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 4345' to 3940'. Mixed and dumped 5 sx. cement from 3940' to 3900'. Pulled casing. Mudded hole to 300'. Set 10' rock bridge from 300' to 290'. Mixed and dumped 20 sx. cement from 290' to 230'. Mudded hole from 230' to 40'. Set 10' rock bridge from 30' to 40'. Mixed and dumped 10 sx. cement from 30' to base cellar.

JAN 3 1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.  
Address Box 304 Great Bend, Ks.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle (~~owner or operator~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 Fourth Natl. Bank Bldg, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 62

My commission expires 11-17-62. Notary Public.

10  
DRILLERS LOG

No. 1 Flora

<b>CASING RECORD</b>	<b>COMPANY:</b> Frontier Oil Company	<b>DESCRIPTION:</b> C SE SW 24-29S-13W
8 5/8" @ 960' w/250 sx cement	<b>CONTRACTOR:</b> Red Tiger Drilling Company	Pratt County, Kansas
5 1/2" @ 4345 w/100 sx cement	<b>COMMENCED:</b> April 12, 1960	<b>ELEVATION:</b> 1923 DF 1926 RB
<b>TOTAL DEPTH:</b> 4735'	<b>COMPLETED:</b> May 3, 1960	

---

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil & Clay	0	40	
Sand & Gravel	40	230	
Shale & Shells	230	460	
Shale Shells	460	1290	
Shale & Shells	1290	1595	
Shale & Lime	1595	1850	
Lime & Shale	1850	2035	
Lime Shale	2035	2165	
Lime & Shale	2165	2315	
Lime	2315	2400	
Lime Shale	2400	2590	
Lime Sandy	2590	2664	
Shale & Lime	2664	2880	
Shale Lime	2880	3065	
Lime & Shale	3065	3210	
Lime Shale	3210	3275	
Lime & Shale	3275	3380	
Lime Shale	3380	3430	
Lime & Shale	3430	3464	
Lime	3464	3555	
Lime & Shale	3555	3630	
Lime Shale	3630	3750	
Lime & Shale	3750	3925	
Lime	3925	4396	
Chert	4396	4421	
Lime	4421	4550	
Lime Chert	4550	4610	
Lime & Shale	4610	4620	
Sand Shale	4620	4629	
Sand	4629	4654	
Lime & Shale	4654	4676	
Shale & Sand	4676	4695	
Shale Sand	4695	4724	
Arbuckle	4724	4735	


---

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

  
George A. Angle

Subscribed and sworn to before me this tenth day of May, 1960.

  
Notary Public

My Commission Expires  
11-17-62